

Flambeau River State Forest and other State Lands


Sustainable Forestry Timber Sales

Includes sales from
Flambeau River State Forest – 10 sales
Pershing Wildlife Area – 3 sales
Sawyer County State Lands – 8 sales

November 7, 2013



Flambeau River State Forest Sale Locator Map



2013 NOVEMBER TIMBER SALES
FLAMBEAU RIVER STATE FOREST
W1613 COUNTY ROAD W
WINTER, WI 54896
(715) 332-5271

Sealed bids for sales in this packet will be received by the Wisconsin Department of Natural Resources, Flambeau River State Forest, at the Flambeau Forest Headquarters, Winter, Wisconsin until **1:30 p.m. on Nov. 7, 2013** and publicly opened immediately thereafter for timber stumpage on the Flambeau River State Forest and other state lands. Sealed bids for the other state lands should also be received at the Flambeau Forest Headquarters. Sealed bids for sales not sold on Nov. 7th will be received at the Flambeau Forest Headquarters until **1:30 p.m. on December 10, 2013**

NEW!!!! NO BID BOND REQUIRED. See Condition #8 under Bidding and Finance.

The sales on the Flambeau River State Forest will use the mill scale ticket system for pulpwood. Sales with saw logs included in the pulp price will also use the mill scale ticket system.

The contractor shall notify a DNR Forester or Forest Technician 3 days prior to beginning work on sale. Before work begins on sale, contractors will be required to have a pre-sale meeting with either a Forest Technician or a Forester.

For inspection of Flambeau River State Forest timber sales for bidding, ATVs will be permitted.

The State does not plow snow on state forest roads. If a sale is located on a state forest road, the contractor is responsible for plowing the snow. The following are state forest roads: Tower Hill, Bass Lake, Price Creek, Hines Grade, Bear Creek, Skinner Creek, and Hervas.

Operational Trees

If an operational tree(s) is(are) cut, the contractor is required to contact the Forester either by leaving a message at the office or by leaving a note in the lock box the day the operational tree(s) is(are) cut.

Forest Certification

The sales in this packet are certified to the standards of the Forest Stewardship Council (FSC) – Certificate #SCS-FM/COC-00070N and the Sustainable Forestry Initiative (SFI) – Certificate #1Y941-S1. Forest products from these sales may be delivered to the mill as “FSC and/or SFI certified” so long as the contractor hauling the forest products is chain-of-custody (COC) certified or covered under a COC certificate from the destination mill. The purchaser is responsible for maintaining COC after leaving the sale area.



All tracts in this packet meet Forest Certification.

TRAINING REQUIREMENT

The purchaser shall ensure that the actual logging contractor engaged in performance of this contract complies with the Wisconsin SFI (Sustainable Forestry Initiative) Training Standard as adopted by the Wisconsin SFI Implementation Committee (SCI). Criteria for the standard can be found at the website www.fistausa.org/sfi_standards or by contacting the Forest Industry Safety & Training Alliance (FISTA). Purchaser agrees to provide documentation to Seller that the training has been attained prior to initiating sale.

SOIL DISTURBANCE AND RUTTING

a. The Purchaser agrees to take all steps and precautions to avoid and minimize soil disturbances, such as soil compaction and rutting. If soil disturbances occur, the Purchaser agrees to work cooperatively to mitigate and repair any and all instances of soil disturbance.

b. Excessive soil disturbance (as defined in Table 1) shall not be permitted. Purchaser agrees to contact Seller in the event of an excessive soil disturbance.

Table 1. Thresholds for soil disturbances.

| <u>Timber Sale Infrastructure</u> | <u>Soil disturbances are excessive if:</u> |
|---|--|
| <i>Roads, Landings, Skid Trails, and General Harvest Area</i> | <ul style="list-style-type: none"> ▪ A gully or rut is 6 inches deep or more and is resulting in channelized flow to a wetland, stream, or lake. |
| <i>Roads, Landings, and Primary Skid Trails</i> | <ul style="list-style-type: none"> ▪ In a riparian management zone (RMZ) or wetland, a gully or rut is 6 inches deep or more and 100 feet long or more. ▪ In an upland area (outside of RMZ), a gully or rut is 10 inches deep or more and 66 feet long or more. |
| <i>Secondary Skid Trails and General Harvest Area</i> | <ul style="list-style-type: none"> ▪ A gully or rut is 6 inches deep or more and 100 feet long or more. |

Note: The depth is to be measured from the original soil surface to the bottom of the depression. If individual lug depressions are visible, the depth would be measured to the lesser of the two depths (the "top" of the lug). The length is measured from the start of the "too deep" section to the end of the "too deep" section. Measurements are not cumulative.

c. Prior to sale completion the Purchaser shall mitigate and repair soil disturbances to the Seller's satisfaction.

For questions on the following properties please contact the person listed:

Other state lands in Sawyer County – Randy Sobraliski (715) 634-9658 ext. 3510

Pershing Wildlife Area – Scott Lindow (715) 748-4955

Flambeau River State Forest – Heidi Brunkow (715) 332-5271 ext. 106.

**FLAMBEAU RIVER STATE FOREST
AND OTHER STATE LANDS
General Sale Conditions**

Bidding and Financing

1. To bid on a tract, each species must be bid on (per cord or MBF) and the minimum total sale value must be met. The advertised value (per cord or MBF) is provided as a reference value only - a bid on each species at its advertised value will automatically meet the minimum total sale value when all species are added together. A bid will be rejected if any individual species/product bid is \$0.
2. A bid must be made on all species and products listed by tract including lump sum sales.
3. All bids must be by tract number and sealed in individual envelopes marked on the outside, Bid on Tract ___.
4. Whole tree (chipping) bids will be adjusted by adding overrun factors to cruised volumes. Notification prior to bidding will be required. Approved areas allowing whole tree logging will be identified along with specific overrun factors to be used. If for any reason the contract is not whole tree harvested, the contractor will pay 25% more than the bid value per species that anticipated whole tree harvest. Whole tree harvest (chipping) includes all wood and bark.
5. All bids will include the following:
 - A. Tract Number
 - B. List of species to be harvested and estimated volume
 - C. Bid price, per unit for each species and product
 - D. Signature and address of each bidder
6. Persons desiring to bid on more than one tract must submit a separate bid for each tract.
7. Bids will be opened in a random order from a draw of the hat. Prior to the reading of a bid, a contractor may elect to withdraw the bid. The contractor or representative of the contractor must declare this at the bid opening before any bids for the specified tract are read.
8. **BID BOND NOT REQUIRED.** Winning bidders will have 6 weeks from the date of the bid opening to submit an acceptable performance bond to the department. If the winning bidder fails to execute the contract and submit an acceptable performance bond, the bidder shall be required to forfeit to the department an amount equal to 10% of the total bid amount. Failure to forfeit the 10% penalty will result in the bidder being considered ineligible to bid on any state timber sales for a two-year period.
9. An Irrevocable Letter of Credit may be used as a Performance Bond. *The expiration date of all letters of credit must be maintained for four full years.* Contact the Forest Headquarters for details regarding the clauses required in the letter.

Contracts & Extensions

1. Contracts must be signed and returned to the Flambeau River State Forest or appropriate property within 30 days of the bid letting.
2. All contracts will be issued for a period of two years, unless otherwise noted. It is understood that all contracts are expected to be completed during the initial contract. Extensions are not automatic.
3. Requests for extensions must be submitted prior to the expiration date of the contract. The performance bond may be retained if requests are not submitted by the expiration date.

Payments

1. Purchaser agrees to make stumpage payments within 30 days of billing, unless otherwise specified in the payment schedule.
2. Late interest penalty – Purchaser agrees to pay a late interest penalty of 1.5% for every 30 days on past due stumpage in excess of the 30 day period. In addition, failure to pay within the 30 day period will result in the Purchaser having to prepay for the remainder of the sale. Two such payment breaches, even on separate State sales, will also result in the purchaser being required to prepay on all state timber sales for a two-year duration.

Utilization Specifications

Those sales without an increased utilization option will have the following standards:

Standard Utilization - Unless otherwise specified, standard specifications will be as follows:

| | |
|-------------------|------------------------------|
| Aspen pulpwood | 4" top diameter |
| Hardwood pulpwood | 4" top diameter |
| Softwood pulpwood | 4" top diameter |
| Hardwood sawlogs | 10" top diameter inside bark |
| Softwood sawlogs | 8" top diameter, inside bark |

Merchantable trees are those that have one or more 100 inch pulpwood sticks with a minimum top diameter of four inches.

Cutting and Skidding Specifications

1. All timber marked or designated for cutting will be utilized whether or not the quantity is more or less than the estimated volume.
2. All decking must be done on the sale if it is not specifically designated. Permission to do otherwise must be obtained from the Forest Superintendent.
3. Any young growth bent or held down by felled trees must be promptly released.
4. The Department of Natural Resources reserves the right to stop operations if unreasonable, excessive, or avoidable damage occurs or will occur. The contractor may be held responsible to repair any or all damage.
5. Although summer logging may be permitted, during wet periods the soils may become soft and susceptible to rutting. Soils may become too wet after storms and extended wet spells. Operations will be suspended during these periods.
6. The Department of Natural Resources may change, suspend or terminate any timber sale contract or portion of contract with no penalties to the State if errors in timber sale planning or designing cause or may cause serious environmental damage, or may cause aesthetic concerns, or are not sound silvicultural practices, or violate any county, state, or federal law or regulation.
7. Any bole damage to residual trees will be considered unnecessary.
8. Trees that are marked with an "X" are not to be cut. They are leave trees. All snags will be reserved unless a safety concern, then the snags will be cut and left for coarse woody debris.
9. **Extra caution is needed to avoid damaging existing pockets of regeneration throughout select cut sale areas.** These pockets of regeneration should not have trees felled into them or skid trails run through them.
10. If collecting firewood for home, a firewood permit is required. **A permit is also required for collection of burls.**

Slash Requirements

1. All slash requirements will be done concurrent with sale operations. For town roads, state forest roads, hunter/walker trails, and ATV/snowmobile trails, all slash and ends will be removed from the roads and ditches concurrently with each truckload.
2. No slash piles from landing operations may be left over 24" above the ground level. Piles shall be spread over the site before leaving.
3. Slash disposal will comply with the State Slash Law, Section 26.12(b), Wisconsin Statutes, and with requests regarding forest fires prevention and suppression made by the seller.

Road and Camps

1. The locations of all roads, landings, and camps must be approved by the Forester prior to construction. A DNR Forester must be contacted at least 48 hours in advance for an appointment.
2. The sale area, including all roads and camps, will be kept neat, clean and free of garbage, oil cans, plastic bottles, and miscellaneous trash throughout the contract period. All residues, including oils and fluids, generated may not be buried or burned, but must be removed from the sale area and disposed of properly.
3. Those merchantable trees removed or damaged as a result of approved road building operations will be utilized.
4. All road entrances must be cleaned up of all roots, stumps, and down trees at the time of construction.
5. It will be the responsibility of the contractor to repair any road damage due to logging.
6. Contractor is required to close roads at designated map locations by placing rocks, stumps and/or cull log barriers, approximately 2 feet apart for a distance of 25 feet completely blocking the road.

7. Road approaches to surfaced roads or other government public roads are the responsibility of the Contractor. Damage to these roads is the responsibility of the Contractor.
8. **The State does not plow snow on state forest roads.** If a sale is located on a state forest road, the contractor is responsible for plowing the snow. The following are state forest roads: Tower Hill, Bass Lake, Price Creek, Hines Grade, Bear Creek, Skinner Creek, and Hervas.

Scaling Specification

1. All bid species of sawlogs will be scaled as such. Pulpwood products cut longer than 8' may be scaled by the board feet and converted to cords as follows: Softwood - 2.44 cds./MBF and Hardwood - 2.20 cds./MBF.
2. All logs will be scaled with the Scribner Decimal C log rule. All logs will be scaled as sawlogs if 50% sound and meet the requirements of a Grade No. 3 log or better in accordance with the National Forest Scaling Handbook. The minimum diameter for a Grade No. 3 log is 10". The maximum trim allowance is 5" unless contractor can demonstrate that market specifications dictate more trim (ties, veneer, etc.). Logs with excessive trim will be scaled at the next highest foot length.
3. Logs will be decked for scaling on pulpwood stringers with the small ends all one way (towards the road) and separated by log length. Decks will not exceed six feet in height and will be accessible for inspection from both sides of the deck.
4. When sap-peeled pulpwood is scaled, 12.5% will be added to hand peeled and stroke delimeter/processor peeled volume, and 16% will be added to ring debarked volume. Scale ticket must state if the load is a peeled product.
5. The mill scale ticket system will be required for pulp. Contractor is required to deposit a scale ticket in the lock box placed on the sale. These tickets are provided by the State Forest and will be filled out in their entirety. The Contractor is also required to deliver a mill ticket to the mill purchasing the forest product. This mill ticket will be returned to the Flambeau River State Forest along with a copy of the mill's scale. The Contractor is responsible for having these mill tickets and scale slips returned to the Flambeau River State Forest in a timely manner. The mill scale slip that corresponds to the lock box ticket must be received at the Flambeau River State Forest Office within 14 days of hauling.
6. If wood is to be yarded at another location other than the sale area, permission must be granted by Forester.
7. Contractors that are required to prepay must at a minimum purchase 5 or more scale tickets at a time, but it is encouraged that a full booklet of 25 scale tickets be purchased.
8. A mill scale ticket must also be placed in the ticket box for loads of scaled logs. The pink copy should be kept with the truck until it reaches the destination, then it can be discarded.

Cordwood Weight Conversion Factors

If a cordwood weight conversion is not provided by the mill purchasing the forest product, the following weight conversion factors will be used in the conversion of weight scale to standard 4' x 4' x 100" cords. Seasoned wood is normally understood to be that which was cut and dried two or more months between April 1 and October 31 before weighing. All other wood should be considered green.

**CORDWOOD WEIGHT CONVERSION FACTORS
POUNDS PER CORD**

| Species | Weight | Species | Weight |
|----------------|---------------|-----------------------|---------------|
| Hemlock | 4800 | Yellow Birch | 5350 |
| Tamarack | 4650 | Hard Maple | 5100 |
| Red Pine | 4500 | Elm | 5000 |
| Jack Pine | 4250 | Balsam Poplar | 4900 |
| Balsam | 4250 | White Birch | 4800 |
| White Pine | 4200 | Ash | 4600 |
| Spruce | 4000 | Soft Maple | 4550 |
| White Oak | 5850 | Aspen | 4500 |
| Red Oak | 5500 | Basswood | 3850 |
| Hickory | 5400 | Mixed Hardwood | 4800 |

Worker's Compensation Law

The contractor (purchaser) shall provide the Department with a Certificate of Insurance indicating that Worker's Compensation Insurance coverage is provided for all of the contractor's (purchaser's) employees working under the contract during its duration. This shall be in the Department's file prior to any performance under the contract. Such certificates of insurance shall further include the condition that the insurer shall notify the Department at the Flambeau River State Forest Headquarters within five (5) days of any change in its terms or twenty (20) days prior to termination.

Seasonal Restrictions

1. No cutting can be done during the months of April, May, and June in selection harvests or pine thinnings due to bark being more easily damaged at these times, unless special permission is granted.
2. Any wood located within 400' of the Flambeau River shall be removed prior to April 1st of each contract year.
3. The State reserves the right to place additional seasonal restrictions on sales as necessary.

Township Restrictions

1. It is the responsibility of the Contractor, to obtain permission from the appropriate Township to deck wood along a town road. Decking on town roads must also be permitted by the forester.
2. All road bans and weight restrictions are the responsibility of the Contractor.

General Conditions

1. All provisions in the contract shall be met before the contract expires. Performance under the contract must proceed in an efficient, workman-like manner, conducive to the orderly completion of the sale. Extensions will only be considered under unusual hardship of circumstances. Details of extension conditions, damage assessments, and other provisions are addressed in the contract which is on file at the Forest Headquarters.
2. Permanent survey monuments shall be left undisturbed. Forest personnel shall be notified if one is encountered during timber sale operations.
3. Extreme caution must be used in sale operations to prevent wildfire. There are requirements outlined in the contract for fire extinguishers and spark arrestors.
4. No skidding, landing, or piling of wood products will take place on the ATV/Snowmobile trail or the State Forest roads without the Forester's approval. The following are State Forest roads: Tower Hill, Bass Lake, Price Creek, Hines Grade, Bear Creek, Skinner Creek, and Hervas. If approval is granted, decking must be at least 10' from the edge of the road or trail.
5. If a snowmobile trail is used for a timber sale operation, 3" of packed snow will be maintained on the snowmobile trail, weather permitting.

The Special Sale Conditions listed for each individual tract and the General Sale Conditions are additions to, or condensations, of a standard timber sale contract that the successful bidder must sign. A sample contract, additional information, maps for each sale, and bid forms may be obtained from the Forest Superintendent, Flambeau River State Forest, W1613, Co. Rd. W, Winter, Wisconsin 54896.

The Department of Natural Resources reserves the right to reject any or all bids.

Tract (4-11) Little Bear Creek

Parts of: NE1/4 and the N1/2SE1/4 of Sec. 5, T38N-R3W

Parts of: NW1/4 and the NW1/4SW1/4 of Sec. 4, T38N-R3W Sawyer County

181 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> | |
|---------------------------|-----------------------------|----------------------------------|----------------------------|
| ¹ Mixed Pulp | 2370 cords | 14.90 | |
| Basswood Pulp | 230 cords | 2.70 | |
| Aspen | 530 cords | 13.60 | |
| ² White Spruce | 15 cords | 11.90 | |
| Sugar Maple | 31 MBF | 217.00 | Minimum Acceptable |
| Red Maple | 5 MBF | 108.00 | <u>Bid for Entire Sale</u> |
| ³ Mixed Saw | 17 MBF | 79.00 | \$51,930.50 |

¹Mixed pulp includes approximately 47% Hard Maple, 32% Red Maple, 9% Ash, 4% Yellow Birch, 4% Elm, and 4% Black Cherry, White Birch, and Ironwood combined.

² White spruce volume includes 1.3 MBF saw.

³Mixed saw is primarily Basswood 67%, Ash 17%, White Birch 9%, Yellow Birch 4%, elm 2%, and black cherry 1%.

Other species not mentioned will be charged at the mixed pulp price or mixed saw price accordingly.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to frozen ground conditions due to wet soil conditions. **No rutting allowed.** General operational period will most likely be December through March.
2. No pole length skidding will be allowed within the select cut or shelterwood areas.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. New road construction must be approved by Forester. Decking will be permitted along woods roads.
4. Existing landings will be used and shall not exceed 200ft X 100ft.
5. No decking of wood will be allowed on the snowmobile trail.
6. Contractor is required to close roads at designated map location by placing logging debris in the following manner: place rocks, stumps and/or cull log barriers, approximately 2 feet apart for a distance of 25 feet completely blocking the road.
7. 3" of packed snow will be maintained on snowmobile trail, weather permitting. The trail will be kept free of debris. No slash shall be left in wetlands or ponds.
8. Cutting will not be allowed in Shelterwood Area until scarification is completed by WDNR during non-frozen conditions. Harvest shall be completed within one year of scarification.
9. If access through Great Lakes Rural NMTC Forest Lands (north of the sale boundary) is desired it shall be obtained by the contractor.
10. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract (4-11) Little Bear Creek Sale



Select Cut Area (107 acres)-Bounded by red paint line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1)snags, 2) trees marked with an orange X. Cut only marked aspen.



Aspen Area (73 acres)-Bounded by yellow paint line. Cut all trees greater than 2 inches except for: 1) hemlock, 2) white pine, 3) oak, 4) cedar, 5) spruce with 2 sticks or less.



Shelterwood Area (1 acre)-Bounded by green paint line. Harvest all merchantable mixed hardwoods except for: 1) hemlock 2) white pine, 3) all aspen, 4) green marked trees, 5) cedar. All unmerchantable stems, except for aspen shall be severed.

Yellow/Y

Yellow paint faces clearcut area

Red/R

Red paint faces select cut area

Green/G

Green paint faces shelterwood area

===

Snowmobile Trail

•••

Ephemeral ponds

Leave Area

swamp hardwood swale/low stocking

↓ ↓

Wet Area

↓ ↓

Approx. Located Section Corner

+

Private Property

PVT.

Proposed road

X X X

--- --

Existing woods road(s)

(B)

Berm to be placed

~ ~ ~ ~

Stream

(L)


Landing

○

Survey Monument

▲ ▲ ▲

Hills



Scale 1:15840
Approx. 4"=1Mile

Tract (13-12) Feleen Fine Sale

Parts of: NESW, NW1/4, W1/2, Sec. 14 T39N-R3W; S1/2SW, SE1/4 Sec. 11 T39N-R3W;
and SESE Sec. 10 T39N- R3W of Sawyer County, WI.

219 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> | |
|-------------------------|-----------------------------|----------------------------------|----------------------------|
| ¹ Mixed Pulp | 1570 cords | \$23.70 | |
| Aspen | 90 cords | \$23.70 | |
| ² Tamarack | 130 cords | \$15.80 | |
| ³ Balsam Fir | 75 cords | \$15.80 | |
| ⁴ Red Pine | 40 cords | \$31.60 | <u>Minimum Acceptable</u> |
| Sugar Maple | 15 MBF | \$189.00 | <u>Bid for Entire Sale</u> |
| ⁵ Mixed Saw | 7 MBF | \$85.00 | \$47,440.00 |

¹Mixed Pulp includes 85% hard maple, 5% red maple, 5% ash, 3% elm, 2% basswood, yellow birch, and ironwood combined.

²Tamarack includes 18 MBF saw.

³Balsam Fir includes 77% balsam fir and 23% black spruce.

⁴Red Pine includes 2 MBF saw.

⁵Mixed Saw includes 43% ash, 29% basswood, 14% red maple, and 14% yellow birch.

Other species not mentioned will be charged at the mixed pulp price or mixed saw price accordingly.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. The timber sale area that is located within the Flambeau River Scenic Management Area shall be harvested during leaf-off conditions only (October 15- March 31st). Equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions. General operational period will most likely be December through March.
2. No pole length skidding will be allowed within the select cut areas or the red pine thinnings.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. Proposed road construction must be located in areas designated on the map. Decking will be permitted along woods roads.
4. Three inches of packed snow must be maintained on the snowmobile trail (weather permitting). All slash and logging debris must be cleared from the trail.
5. All pine products cut or piled between May 1st and August 1st must be removed from the site within 30 days.
6. Slash and logging debris will not be left across the blue line. All logging debris shall be kept off of and out of the ditch lines of the snowmobile/ATV trail and township roads.
7. Avoid damage to government survey monuments.
8. Within the tamarack seed tree area there is a powerline that runs along the eastern boundary. Stay back from line at least 40 feet.
9. Slash within 100 feet of Hwy 70, Oxbo Road, Feleen Road, and snowmobile trail shall be lopped and scattered to within 2 feet of the ground.
10. Northern portion of sale located within the Flambeau River Scenic Management Area shall be accessed by woods road, NOT Snowmobile/ATV Trail.
11. Contractor is required to close road at the locations designated on the map by placing logging debris, per sale prospectus.
12. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract (13-12) Feleen Fine Sale – 219 acres



Select Cut Area (201 acres) - Bounded by red paint line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1) snags 2) cull trees 3) trees marked with an orange X. Cut only marked aspen. Sever all balsam fir 2 inches and greater. Leave all balsam fir within 100ft. of the sale boundaries along STH 70.



Aspen Area (10 acres) -Bounded by yellow paint line. Cut all trees greater than 2 inches except for: 1) hemlock, 2) white pine, 3) oak.



Red Pine Thinnings (6 acres) -Bounded by red paint line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems. Leave, do not cut 1) snags 2) cull trees 3) trees marked with an orange X.



Tamarack Seed Tree(1 acre) - Bounded by green paint and powerline (Stay 40 feet back!). Harvest all trees greater than 2 inches except for green marked trees.



Tamarack Clearcut (<1 acre) -Bounded by yellow paint. Harvest all trees greater than 2".

Blue Blue paint indicates private property

Yellow Yellow paint faces aspen area

Red Red paint faces select cut and red pine thinnings


Green Green paint faces seed tree

R/Y Red paint faces select/Yellow paint faces aspen area

Shaded area is located within FRSF Scenic Area

Legend

- Building
- Proposed Berm
- Gates
- Landings
- Turnarounds
- Wet Area
- Section Corner
- Rivers & Streams
- Roads**
- STATE
- TOWNSHIP
- ATV/Snowmobile
- Open Roads
- Woods trails
- Proposed Road
- Powerline
- Private Property



Tract (14-12) Bell Bottoms Sale
Parts of: SE1/4, NE1/4 Sec. 9 T39N R3W
Sawyer County, WI

Acres: 113

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> | |
|-------------------------|-----------------------------|----------------------------------|--|
| ¹ Mixed Pulp | 670 cords | \$30.30 | |
| ² Tamarack | 350 cords | \$16.40 | |
| | | | Minimum Acceptable <u>Bid for Entire Sale</u> \$26,041.00 |

¹Mixed pulp includes 82% hard maple, 12% red maple, 5% ash and 1% basswood and yellow birch combined and 12 MBF hard maple, 4 MBF red maple, and 3 MBF Misc. Saw(includes 25% basswood and 75% ash).

²Tamarack includes 82% tamarack and 16% black spruce.


*Other species not mentioned will be charged at the mixed pulp price.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.


SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to frozen ground conditions due to wet soil conditions. General operational period will most likely be December through March.
2. No pole length skidding will be allowed within the select cut area.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. New road construction must be approved by Forester. Decking will be permitted along woods roads. Decking along Old 70 would need to be approved by the Town of Draper.
4. Private property borders a portion of the eastern side of the sale. Slash and logging debris will not be left across the blue line onto private property.
5. Contractor is required to close roads at the designated locations on the map by placing logging debris, per sale prospectus.
6. Slash that is within 100 feet of Hwy 70 and Old Hwy 70 shall be lopped and scattered to within 2 feet of the ground.
7. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract (14-12) Bell Bottoms Sale- 113 acres




Select Cut Area (102 acres)-Bounded by red paint line and blue private line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1) snags, 2) cull trees, 3) trees marked with an orange X. Cut only **marked** aspen.



Tamarack Area (11 acres)-Designated by orange marked center line. Cut all trees greater than 2 inches within 100 feet of both sides of the center line except for: 1) hemlock, 2) white pine, 3) oak. (Strips will be 200 feet wide from edge to edge). *Total stand is 39 acres. Area to be cut is 11 acres.*

- Red** Red paint faces select cut
- Blue** Blue paint faces sale area along private property
- Orange** Orange marks indicate center of strip
- Leave** Swamp conifer/open wetland



Tract (15-12) E Easy Sale

Parts of: SW, NW, W1/2NE of Sec. 2 T39N R3W

Parts of: N1/2NW of Sec. 11 T39N R3W

Parts of: E1/2NW, NE, S1/2SE, NWSE of Sec. 3 T39N R3W

Sawyer County, WI

Acres: 201

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> |
|-------------------------|-----------------------------|----------------------------------|
| ¹ Mixed Pulp | 700 cords | \$30.00 |
| Aspen | 1960 cords | \$18.30 |
| ² Balsam Fir | 400 cords | \$12.20 |

Minimum Acceptable
Bid for Entire Sale
\$61,748.00

¹Mixed pulp includes 59% hard maple, 36% red maple, 2% elm, 3% ash, basswood, ironwood, oak and yellow birch. Also includes 1340 bd. ft. of mixed sawlog.

²Balsam Fir includes very small amount of White Spruce saw.


Other species not mentioned will be charged at the mixed pulp price.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to frozen ground conditions due to wet soil conditions. **No rutting allowed.** General operational period will most likely be December through March.
2. No pole length skidding will be allowed within the select cut area. If pole skidding in aspen areas, landing size will not exceed 100' by 200'.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. New road construction must be approved by Forester. Decking will be permitted along woods roads. Tuscobia Trail will not be used to haul wood.
4. All wood harvested along the Tuscobia trail shall be decked behind the 50 foot buffer.
5. Berms are to be placed/replaced at end of sale at indicated positions on the map.
6. Multiple stick nests can be found throughout the site. Damage to nest trees should be avoided.
7. Prior to harvesting the area north of the Tuscobia Trail, the contractor is required to obtain a permit for crossing the trail from the Tuscobia Trail Manager. There is a 50 foot no cut buffer along the trail that has been lined out with yellow paint.
8. The Tuscobia Trail Crossing is located on map. Moving wood across the Tuscobia trail shall only be conducted from 6am to 6pm on Mon. thru Fri., unless special permission is granted from Tuscobia Trail Manager. A flashing light shall be present during the moving of equipment across the Tuscobia Trail.
9. A temporary in-stream crossing is required for access to this timber sale. All requirements of this crossing shall be followed by the contractor.
10. 3" of packed snow will be maintained on snowmobile trail, weather permitting. The trail will be kept free of debris. Signs shall be posted along the trail warning traffic of logging equipment.
11. All slash that is located within 100 feet of Hwy EE, hunter walker trail, and the Tuscobia Trail shall be lopped and scattered to within 2 feet of the ground.
12. No slash or logging debris will be left across the blue line onto private land.
13. **All additional restrictions listed in prospectus and standard contract apply unless specified.**


Tract (15-12) E Easy Sale- 201 acres


 **Select Cut Area (47 acres)-** Bounded by red paint line and Hwy EE. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1) snags, 2) cull trees, 3) trees marked with an orange X. Cut only **marked** aspen.

 **Aspen Area (154 acres)-** Bounded by yellow paint line, Hwy EE, and blue paint line. Cut all trees greater than 2 inches **except for:** 1) hemlock, 2) white pine, 3) oak, 4) spruce, 5) cedar, 6) cherry. There is a 50 foot no cut buffer along the Tuscobia Trail, painted in yellow.


Yellow Yellow paint faces aspen area
 Red Red paint faces select cut
 Blue Blue paint faces aspen area (indicates private property beyond)
 R/Y Red paint faces select/Yellow paint faces aspen area


Legend

-  Tuscobia Trail Crossing
-  Stream
-  Wet Areas
-  Turn Around
-  Stream Crossing
-  Gate
-  Proposed Berm
-  Section Corner
-  Leave/Open Area
-  Private

-  ATV Snowmobile
-  Hunter Walker
-  Woods trails

Other Roads

-  STATE
-  COUNTY
-  TOWNSHIP
-  Proposed Road



Tract (16-12) Nedli Doodily Sale

Parts of: SWNE, SENW, NESW, NWSE, SWSW Sec. 21 T38N R3W

Parts of: W1/2 Sec. 28 T38N R3W

Parts of: SENE, NESE, NESW Sec. 29 T38N R3W

Sawyer County, WI

260 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> |
|-------------------------|-----------------------------|----------------------------------|
| ¹ Mixed Pulp | 1770 cords | \$25.10 |
| Basswood | 120 cords | \$3.60 |
| Aspen | 400 cords | \$25.10 |
| White Spruce | 160 cords | \$20.50 |
| Balsam Fir | 100 cords | \$14.90 |
| Sugar Maple | 13 MBF | \$240.00 |
| ² Mixed Saw | 9 MBF | \$114.00 |

Minimum Acceptable
Bid for Entire Sale
\$63,815.00

¹Mixed pulp includes 46% hard maple, 29% red maple, 11% ash, 7% yellow birch, and 7% ironwood and elm combined.

²Mixed Saw includes 8% red maple, 32% ash, 45% basswood, 15% yellow birch.

Other species not mentioned will be charged at the mixed pulp price or misc. saw price accordingly.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions. General operational period will most likely be December through March.
2. No pole length skidding will be allowed within the select cut areas.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. New road construction must be approved by Forester. Decking of wood shall be kept outside the ditch line of the snowmobile trail.
4. Three inches of packed snow must be maintained on the snowmobile trail (weather permitting). All slash and logging debris must be cleared from the trail. Slash that is within 100 feet of the snowmobile trail must be lopped and scattered to within 2 feet of the ground by the contractor.
5. If decking is done on Nedli Road, which is an open road that doubles as an ATV/snowmobile trail, all slash and ends will be removed from the road and ditches concurrently with each truckload. No slash will be left in the ditches along Nedli Road.
6. Slash that is within 100 feet of Nedli Road will be lopped and scattered to within 2 feet of the ground by the contractor.
7. Contractor will be required to close roads at locations designated on the map by placing logging debris, per sale prospectus.
8. No slash or logging debris will be left across the blue line onto private land.
9. **It is the responsibility of the contractor to obtain permission to access sale through private property.**
10. Avoid government survey monuments illustrated on map.
11. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract (16-12) Nedli Doodily Sale – 260 acres




Select Cut Area (225 acres)-Bounded by red paint line, blue paint line, and ATV/Snowmobile Trail. Harvest all orange marked trees within the designated boundaries. Sever all orange marked non-merchantable stems (canopy gaps). Leave, do not cut 1) snags 2) cull trees 3) trees marked with an orange X. Cut only marked aspen.




Aspen Area (35 acres)-Bounded by yellow paint line. Cut all trees greater than 2 inches except for: 1) hemlock, 2) white pine, 3) oak.

Blue Blue paint indicates private property
Yellow Yellow paint faces aspen area
Red Red paint faces select cut
R/Y Red paint faces select/Yellow paint faces aspen area



Legend

- Stream
- Ⓟ Existing Berm
- ▲ Gates
- Ⓣ Turnarounds
- ☼ Wet Area
- ⊙ Survey Marker
- ⊕ Section Corner
- ▭ Private Prop.
- Roads**
- ▬ COUNTY
- ▬ TOWNSHIP
- ↔ ATV Snowmobile
- ▬ Open Roads
- - - Woods trails



Tract (1-13) Loopy Ski Trail Sale

Parts of: N1/2NW of Sec. 15, SE, SW, S1/2NW of Sec. 10, E1/2SW, NWSE, SWNE of Sec. 3, W1/2SE, SWNE, E1/2SW of Sec. 2, NW, S1/2NE, N1/2SE of Sec. 11 and NWSW, SWNW of Sec. 12, T38N-3W, Sawyer County.

246 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> | |
|-------------------------|-----------------------------|----------------------------------|----------------------------|
| ¹ Mixed Pulp | 2140 cords | 27.90 | |
| Basswood | 50 cords | 4.70 | |
| Aspen | 660 cords | 27.90 | |
| ² Spruce | 140 cords | 16.00 | |
| Hard Maple | 5 MBF | 255.00 | |
| Red Maple | 5 MBF | 128.00 | Minimum Acceptable |
| Ash | 9 MBF | 94.00 | <u>Bid for Entire Sale</u> |
| White Birch | 20 MBF | 94.00 | \$ 85,581.00 |
| ³ Mixed Saw | 3 MBF | 115.00 | |

¹Mixed pulp includes 41% hard maple, 24% red maple, 15% ash, 4% yellow birch, 14% white birch, and 2% elm, ironwood, cherry, and oak.

²Spruce includes 88% spruce and 12% balsam fir.


³Mixed Saw includes 2 MBF Basswood and 1 MBF Yellow Birch.

Other species not mentioned will be charged at the mixed pulp or mixed saw price accordingly.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Shaded areas shall be harvested between September 9th and December 13th of contract period. (Due to ski trail and Flambeau River Scenic Management Area restrictions.) In the remaining portion of the sale equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions. General operational period for these areas will most likely be December through March.
2. No pole length skidding will be allowed in the shelterwood or select cut areas.
3. The ski trail will **NOT** be used as a main haul road and skidding on the trail should be limited. The use of high speed skid trails is optional, the routes have been highlighted on the map. The condition of the ski trail is the responsibility of the contractor, it will be returned to the condition it was or better. The contractor will be responsible for leveling the trail at the end of each year of contract.
4. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. Decking will be permitted along woods roads. Any decking of wood along ATV/snowmobile trail shall not impede the traffic.
5. Slash that is within 100 feet of open road, ski trail, ATV/Snowmobile trail shall be lopped and scattered to within 2 feet of the ground.
6. Contractor is required to close road at the locations designated on the map by placing logging debris, per sale prospectus.
7. No new access points will be permitted.
8. All wood decked within the shaded area, Flambeau River Scenic Area, shall be removed prior to Dec. 13 of each year of contract.
9. Contractor must notify DNR prior the September prior to harvesting. Birch Shelterwood area shall not be harvested until the DNR completes a scarification treatment. Harvest shall be completed within one year of the scarification.
10. All logging debris shall be kept off of and out of the ditch lines of the ski trail, ATV/Snowmobile trail, and open roads.
11. Turn around placement can be modified with approval from Forester.
12. **All additional restrictions listed in prospectus and standard contract apply unless specified.**



- Legend**
- HighSpeedSkiTrail
 - ProposedRoad
 - Opening
 - Existing Rock Ford
 - Existing Berm
 - Gate
 - Wet Area
 - Steep Slope
 - Proposed Berm
 - Turn Around
 - Section Corner
- Roads**
- ATV/Snowmobile
 - Ski Trail
 - Open Roads
 - Woods trails
 - Stream

Tract (1-13) Loopy Ski Trail Sale

- Select Cut Area (206 acres)**- Bounded by red paint line and ATV trail. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1) snags 2) cull trees 3) trees marked with an orange X. Cut only marked aspen.
- Aspen Area (38 acres)**- Bounded by yellow paint and ATV trail. Cut all trees greater than 2 inches except for: 1) hemlock, 2) white pine, 3) oak, 4) cedar, 5) cherry, 6) red pine. Cut all orange marked trees. (Note: There is a spruce/aspen stand on the northeast end of the sale that has a red boundary. Cut R/Y boundary trees. This stand will follow the guidelines above.)
- Shelterwood Area (2 acres)**- Bounded by green paint line. Harvest all trees greater than 2 inches except for: 1) hemlock, 2) white pine, 3) all aspen, 4) green marked trees, 5) cedar. All unmerchantable stems, except for aspen shall be severed.


R Red paint faces select cut area
 Y Yellow paint faces aspen area
 G Green paint faces shelterwood area

1 mile from Flambeau Hills Parking Lot

2.4 miles from Hwy W to Gate

2.3 miles from Flambeau Hills Parking Lot

03|02
10|11
.5 miles
 .2 miles



Tract (3-13) Bass Lake Sale

Parts of: SESW, S1/2SE of Sec. 12 and SE1/4, NE1/4, E1/2NW of Sec. 13, Sawyer County.

131 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> | |
|-------------------------|-----------------------------|----------------------------------|----------------------------|
| ¹ Mixed Pulp | 1015 cords | 26.40 | |
| Basswood | 65 cords | 4.40 | |
| Aspen | 40 cords | 26.40 | |
| Hard Maple | 9 MBF | 204.00 | |
| Ash | 11 MBF | 102.00 | <u>Minimum Acceptable</u> |
| ² Mixed Saw | 11 MBF | 92.00 | <u>Bid for Entire Sale</u> |
| | | | \$32,504.00 |

¹Mixed pulp includes 68% hard maple, 8% red maple, 20% ash, 4% yellow birch, white birch and ironwood combined.

²MX saw is 3 MBF red maple, 4 MBF basswood, 1 MBF yellow birch, and 3 MBF white birch.


Other species not mentioned will be charged at the mixed pulp/saw price.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted very dry to frozen ground conditions due to wet soil conditions. General operational period will most likely be December through March.
2. No pole length skidding will be allowed in the select cut areas.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. Decking will be permitted along woods roads. Any decking of wood along Bass Lake Road shall be located outside the ditch line of the road.
4. Proposed roads shall be located in designated location due to wet soils and other restrictions.
5. Slash that is within 100 feet of open road, parking lot, or hunter walking trails shall be lopped and scattered to within 2 feet of the ground.
6. Contractor is required to close road at the locations designated on the map by placing logging debris, per sale prospectus.
7. Woods roads to the east of the sale area shall not be used due to State Natural Area Restrictions.
8. All logging debris shall be kept off of and out of the ditch lines of the hunter walking trails, open roads, and around parking lot.
9. 3" of snow shall be maintained on Tower Hill Road, which is the snowmobile trail, weather permitting.
10. Do not use roads within Old Growth Study Area and do not leave tops across redline into study area.
11. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract (3-13) Bass Lake Sale



Select Cut Area (131 acres)-Bounded by red paint line and Bass Lake Road. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1) snags 2) cull trees 3) trees marked with an orange X. Cut only marked aspen.

Red Red paint faces select cut
Leave Hemlock/Black Ash Wet Area

Legend

■ Proposed Berm

☙ Wet Area

▲ Gate

⊕ Section Corner

▨ Old Growth Study Area

Roads


▬ COUNTY

▲▲▲▲ Hunter Walker

▬▬▬ Open Roads

- - - - Woods trails

* * * Proposed Road



Tract (6-13) You're Breaking My Heart

Parts of: S1/2NW, N1/2SW of Sec. 35, NW, NE, N1/2SW, N1/2SE of Sec. 34, NESE, SENE of Sec. 33, SESW, SWSE of Sec. 27, of T38N-3W, Sawyer County.

179 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> |
|-------------------------|-----------------------------|----------------------------------|
| ¹ Mixed Pulp | 1300 cords | 22.50 |
| Basswood | 110 cords | 3.80 |
| Aspen | 530 cords | 22.50 |
| ² Spruce | 960 cords | 18.80 |

Minimum Acceptable

Bid for Entire Sale

\$59,641.00

¹Mixed pulp includes 28% hard maple, 39% red maple, 26% ash, 4% white birch and 3% yellow birch, ironwood, and cherry pulp combined. This volume also includes 3 MBF hard maple, 2 MBF red maple, 1 MBF basswood, and 5 MBF ash.

²Spruce volume includes 43 MBF spruce and 130 cords of balsam fir.

Other species not mentioned will be charged at the mixed pulp price.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to frozen ground conditions due to wet soil conditions. General operational period will most likely be December through March.
- 2.
3. No pole length skidding will be allowed the spruce plantations or select cut areas.
4. New road construction will be necessary and will need prior approval. Existing woods roads will be used.
5. Slash that is within 100 feet of Hwy M shall be lopped and scattered to within 2 feet of the ground.
6. Contractor is required to close road at the locations designated on the map by placing logging debris, per sale prospectus.
7. All conditions of the in-stream crossing permit will be followed by the contractor.
8. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

(Tract 6-13) You're Breaking My Heart
 179 acres



Select Cut Areas (82 acres)- Bounded by red paint line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps).



Aspen/Red Maple Areas (71 acres)- Bounded by yellow paint line. One area is bounded by red as indicated on map. Cut all trees greater than 2 inches **except for:** 1) hemlock, 2) white pine, 3) oak, 4) spruce with 2 sticks or less.




Plantation Thinning (26 acres)- Bounded by red paint and hardwood. Harvest all trees marked with orange paint.

Red and R-paint line faces select cut area and plantation thinning and 1 aspen/red maple area
Yellow and Y-paint line faces aspen/red maple area
R/Y-paint line between aspen and select cut/plantation areas

Legend

- Proposed Berm
- ▲ gate
- ☙ Wet Area
- ⊕ Section Corner
- Stream Crossing
- Rivers and Streams
- Roads
- ▬ COUNTY
- - - Woods Roads
- * * Proposed Roads



Tract 7-13 (Wind Tunnel)

Parts of: NW, SW Sec. 26; SE, SWNE, NESW Sec. 27; NE Sec. 34
T39N-R3W Sawyer County

212 Acres

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> | |
|-------------------------|-----------------------------|----------------------------------|----------------------------|
| Mixed Pulp ¹ | 1700 cds | 26.10 | Minimum Acceptable |
| Basswood Pulp | 150 cds | 3.80 | <u>Bid for Entire Sale</u> |
| Sugar Maple | 19 MBF | 258.00 | \$ 52,273.00 |
| Basswood | 11 MBF | 105.00 | |
| Mixed Saw ² | 11 MBF | 116.00 | |


¹Mixed pulp includes approx. 77% of sugar maple, 5% of red maple, 7% of ash, 8% yellow birch, and 3% ironwood, elm, cherry. ²Mixed saw includes 2 MBF of red maple, 4 MBF of ash, 4 MBF of yellow birch and 1 MBF of cherry. Species not listed will be charged the mixed pulp price or mixed saw price.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.

SPECIAL SALE CONDITIONS:


1. This sale is located in the Flambeau River Scenic Area, so equipment use will be restricted to very dry or frozen conditions during the leaf-off period only (Oct. 15th – Mar. 31st). Some areas will require frozen conditions.
2. No pole length skidding will be allowed in the select cut area.
3. Existing woods roads will be used. No new road construction. When widening the existing roads, the roads shall be widened on the side away from the Flambeau River.
4. Location of turn arounds is limited to proposed layout shown on prospectus map. Modifications can be made with approval from Forester.
5. Slash that is within 100 feet of Flambeau River will be lopped and scattered to within 2 feet of the ground by the contractor.
6. No slash will be left on or in ditch lines of the State Forest Access Road. Any damage done to the State Forest Access Road or the ditch lines is the responsibility of the contractor.
7. Do not harvest current fallen dead trees (Coarse Woody Debris – CWD). The CWD can be cut and moved for skidding purposes, but it must remain on site. Do not cut snag tree, unless it is a safety concern. Only harvest orange marked trees within the wind-damaged pockets illustrated on prospectus map. Map shows approximate locations of the wind damaged pockets.
8. It is the responsibility of the contractor to plow snow on the state forest access road.
9. Avoid government survey monuments illustrated on prospectus map.
10. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract 7-13 (Wind Tunnel Sale) – 212 acres



Select Cut Area (212 acres) -Bounded by red paint line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps). Leave, do not cut 1) snags, 2) cull trees, 3) trees marked with an orange X.

Red Red paint is the outside boundary of entire sale. The red paint faces the select cut area.
SB Black spruce **Hem** Hemlock
PW White pine **UB** Upland brush



Tract (11-13) DW Sale

Parts of E1/2NE, SWNE, SE, E1/2SW Sec 5 T36N R4W

Parts of NWNE Sec 8 T36N R4W Rusk County

Acres 123

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value/Unit</u> |
|-------------------------|-----------------------------|----------------------------------|
| ¹ Mixed Pulp | 1000 cords | 26.10 |
| Basswood | 150 cords | 3.90 |
| Aspen | 400 cords | 26.10 |
| Sugar Maple | 9 MBF | 291.00 |
| Red Maple | 7 MBF | 146.00 |
| Ash | 6 MBF | 107.00 |
| Basswood | 15 MBF | 126.00 |
| Mixed Saw | 1 MBF | 131.00 |

Minimum Acceptable
Bid for Entire Sale
\$43,429.00

¹Mixed pulp includes 52% Sugar Maple, 25% Red Maple, 22% Ash, and 1% misc. species.


All other species not mentioned will be charged at the mixed pulp price or misc. saw price accordingly.

The performance bond will be 15% of the total sale value. Contract length is approximately two years.


SPECIAL SALE CONDITIONS:

1. Equipment use will be restricted to very dry or frozen ground conditions due to wet soil conditions. **No rutting allowed.** General operational period will most likely be December through March. Harvesting within the Flambeau River Scenic Area will be restricted to October 15th to April 1st.
2. No pole length skidding will be allowed in select cut area.
3. Existing woods roads will be used. Improvements will need to be made on several portions of the existing road system. New road construction must be approved by Forester. Decking will be permitted along woods roads.
4. All wood decked within the Flambeau River Scenic Management Area, shall be removed prior to April 1st of each contact year.
5. Slash that is located within 100 feet from Flambeau Road shall be lopped and scattered to within 2 feet of the ground.
6. No slash or logging debris is allowed in the ditches of any township road and/or forest access road. It is the responsibility of the contractor to keep the ditch lines clear of debris.
7. Roads are not to exceed 15 ft. in width without permission from the Forester.
8. Contractor is required to close roads at locations designated on map by placing logging debris per sale prospectus.
9. No slash or logging debris will be left across blue line onto private land.
10. **All additional restrictions listed in prospectus and standard contract apply unless specified.**

Tract (11-13) DW Sale (123 acres)



Select Cut Area (86 acres)-Bounded by red paint line. Harvest all orange marked trees within the designated boundaries. Sever all orange marked unmerchantable stems (canopy gaps).
 Leave, do not cut 1) snags 2) cull trees 3) trees marked with an orange X. Cut only **marked** aspen.



Aspen Area (37 acres)-Bounded by yellow paint line. Cut all trees greater than 2 inches **except for:** 1) hemlock, 2) white pine, 3) oak, 4) spruce with 2 sticks or less.

- Yellow** Yellow paint faces aspen area.
- Red** Red paint faces select cut.
- R/Y** Red paint faces select cut/Yellow paint faces aspen area
- Blue** Blue paint faces Flambeau River State Forest property.
- RMZ** Riparian Management Zone




0 0.25 0.5 1 Miles

Scale 1:15840

Legend

- Town Road
- Flambeau River Scenic Area
- Section Corners
- Woods Roads
- Streams
- Proposed Turnaround
- Gate
- Steep Slope
- Proposed Berm
- Rusk/Sawyer Co. Line



State of Wisconsin
Department of Natural Resources
Pershing Wildlife Area

Timber Sale Prospectus
Tract # P1-13

Section 10 T32N R4W

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value / Unit</u> |
|---------------------|-----------------------------|------------------------------------|
| Aspen | 300 cords | \$ 22.50 / cd |
| Misc. Hardwood | 200 cords | \$ 22.50 / cd |
| Balsam Fir | 40 cords | \$ 13.50 / cd |
| Misc. hardwood Logs | 4 MBF | \$ 108.00 / MBF |

For questions on this sale, please contact:
Scott Lindow at the Medford Ranger
Station. 715-748-4955

Minimum Acceptable Bid for Entire Sale: \$ 12,222.00

NOTE: The successful bidder will be required to provide a performance bond in the amount of 15% of the sale value. Contract length is approximately two years.

Harvesting Prescription:

Clear Cut Area: Harvest all trees 2" DBH and larger. **EXCEPT: Red Oak, White Pine, Spruce, Hemlock and green paint marked trees.**

Northern Hardwood Selection Area: Harvest all orange paint marked trees.

Swamp Hardwood Seed Tree Area: Harvest all trees 2" DBH and larger. **EXCEPT: Red Oak, White Pine, Spruce, Hemlock and green paint marked trees.**

ALL AREAS: Utilize all cut trees that will make one or more 100" pulpwood stick to a 4" top D.I.B. Harvesting will only be permitted between December 1 and February 29, or during periods of frozen ground condition.

Integrated Resource Considerations:

Any road location and construction is subject to review and approval by the Department of Natural Resources. Prior to the timber sale closeout procedure, all forest trails and logging roads used in the harvesting operation must be free of slash, logging debris, ruts and be level.

Pershing Wildlife Area Timber Sale


Section 10 T 32N R4W

Tract P 1-13 28 acres

Aspen Clearcut 17 acres

Northern Hardwood Selection Harvest 7 acres

Swamp Hardwood Seed Tree 4 acres



LEGEND

STAND 1 - ASPEN CLEAR CUT

STAND 2 - NORTHERN HARDWOOD
SELECTION HARVEST

STAND 3 - SWAMP HARDWOOD
SEED TREE

XXXXXX - FENCE

SCALE - 8" = 1 MILE



State of Wisconsin
Department of Natural Resources
Pershing Wildlife Area

Timber Sale Prospectus
Tract # P2-13

Section 3 & 4 T32N R4W

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value / Unit</u> |
|---------------------|-----------------------------|------------------------------------|
| Aspen | 200 cords | \$ 20.90 / cd |
| Misc. Hardwood | 140 cords | \$ 20.90 / cd |
| Balsam Fir | 50 cords | \$ 12.60 / cd |
| Basswood | 10 cords | \$ 3.60 / cd |
| Misc. hardwood Logs | 8 MBF | \$ 108.00 / MBF |

Minimum Acceptable Bid for Entire Sale: \$ 8636.00

CALL SCOTT LINDOW AT THE MEDFORD RANGER STATION TO MAKE AN APPOINTMENT AND OBTAIN ACCESS THROUGH THE WATERFOWL REFUGE TO REVIEW THE SALE AREA PRIOR TO BIDDING, 715-748-4955.

NOTE: The successful bidder will be required to provide a performance bond in the amount of 15% of the sale value. Contract length is approximately two years.

Harvesting Prescription:

Clear Cut Area: Harvest all trees 2" DBH and larger. **EXCEPT:** Oak, White Pine, Spruce, Hemlock, Elm, and Hickory.

Northern Hardwood Selection Area: Harvest all orange paint marked trees.

ALL AREAS: Utilize all cut trees that will make one or more 100" pulpwood stick to a 4" top D.I.B. Harvesting will only be permitted between December 1 and February 29, or during periods of frozen ground condition.


Integrated Resource Considerations:

Any road location and construction is subject to review and approval by the Department of Natural Resources. Prior to the timber sale closeout procedure, all forest trails and logging roads used in the harvesting operation must be free of slash, logging debris, ruts and be level.

- Special Concern: Access to this sale is across a pond dike. Care needs to be used to not damage the dike or the water control structure (ex. drive frost into tube and freeze it up or damage the structure).


Pershing Wildlife Area Timber Sale
Section 3 & 4 T32N R4W
Tract P2-13 26 acres

Aspen Clearcut 24 acres
Northern Hardwood Selection Harvest 2 acres



CALL SCOTT LINDOW AT THE MEDFORD RANGER STATION
TO MAKE AN APPOINTMENT AND OBTAIN ACCESS THROUGH
THE WATERFOWL REFUGE TO REVIEW THE SALE AREA PRIOR
TO BIDDING, 715-748-4955.

Private Land



| Legend | |
|--------|-------|
| | Road |
| | fence |



State of Wisconsin
Department of Natural Resources
Pershing Wildlife Area

Timber Sale Prospectus
Tract # P3-13

Section 1 T32N R4W

| <u>Species</u> | <u>Estimated Volume</u> | <u>Advertised Value / Unit</u> |
|----------------|-----------------------------|------------------------------------|
| Aspen | 360 cords | \$ 20.90 / cd |
| Misc. Hardwood | 50cords | \$ 20.90 / cd |
| White Birch | 10 cords | \$ 20.90 / cd |

For questions on this sale, please contact:
Scott Lindow at the Medford Ranger
Station. 715-748-4955

Minimum Acceptable Bid for Entire Sale: \$ 8,778.00

NOTE: The successful bidder will be required to provide a performance bond in the amount of 15% of the sale value. Contract length is approximately two years.

Harvesting Prescription:

Harvest all trees 2" DBH and larger. **EXCEPT:** Oak, White Pine, Spruce, Hemlock, Elm, Hickory.

ALL AREAS: Utilize all cut trees that will make one or more 100" pulpwood stick to a 4" top D.I.B. Harvesting will only be permitted between December 1 and February 29, or during periods of frozen ground condition.


Integrated Resource Considerations:

Any road location and construction is subject to review and approval by the Department of Natural Resources. Prior to the timber sale closeout procedure, all forest trails and logging roads used in the harvesting operation must be free of slash, logging debris, ruts and be level.

- Special Concern: Access to this sale is across a pond dike. Care needs to be used to not damage the dike or the water control structure (ex. drive frost into tube and freeze it up or damage the structure).
- Contractor must replace the berm on the trail near the corner of Hooker Rd. At the conclusion of the harvest.

Pershing Wildlife Area Timber Sale
Section 1T32N R4W
Tract P3-13 18 acres

Aspen Clearcut 18 acres



SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H02-10
 Sections, 16,17,20 T40N R7W

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|------------------|------------------|--------------|---|----------|
| Mixed Hardwood | 825 cds | \$15.00/cd | | |
| Aspen | 1000 cds | \$20.00/cd | | |
| Red Pine (mixed) | 50 cds | \$30.00/cd | Contains 25 cds pw pulp, 11 cds pr pulp and 6 MBF pr logs | |
| Oak | 150 cds | \$12.00/cd | | |
| Mixed Hardwood | 22 MBF | \$100.00/MBF | | |
| OAK | 3 MBF | \$250.00/MBF | | |
| White Pine | 11 MBF | \$100.00/MBF | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions: leaf off logging only, with no cutting after March 15th

Sale Area

Cut all orange marked oak, red pine and white pine. Also cut all merchantable aspen, and mixed hardwood within sale area. Sever all other mixed hardwood stems 1 inch and larger. Utilize pulp wood to a 4 inch top, hardwood saw logs to 10" DIB and pine saw logs to a 9" DIB. All logs to be scaled on the landing, piled small end out.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.


SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

State Lands Timber Sale
Chippewa Flowage Property
SENW, SWNE, E1/2SE, SEC 17; NWSW SEC 16;
NENE SEC 20; T40N R7W
Tract H0210 Sale# _____ 88 Acres



Legend

- Property Boundary
- ▣ SALE AREA

4 inches = 1 mile

SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H02-11
 Section, SWSE Sec. 6, NE ¼ Sec. 7

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|---------------------------------|------------------|--------------|---|----------|
| ASPEN | 450 cds | \$20.00/cd | | |
| MIXED HARDWOOD | 700 cds | \$20.00/cd | | |
| OAK | 230 cds | \$12.00/cd | | |
| WHITE BIRCH | 150 cds | \$20.00/cd | | |
| PINE- mixed product and species | 20 cds | \$20.00/cd | This volume contains both red pine and white pine. Also approximately 4 MBF of logs | |
| MIXED HARDWOOD | 7 MBF | \$100.00/MBF | | |
| OAK | 26 MBF | \$200.00/MBF | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions: Frozen Ground logging only

Sale area

Utilize pulp wood down to a 4 inch diameter top. Utilize hardwood saw logs down to 10 inches D.I.B. inside the bark, and 9 inches D.I.B. for pine. All logs are to be scaled on the landing by state forester and should be piled with small end out.

Select Cut Area

Cut all orange marked oak, basswood, and pine. Also cut all merchantable aspen, white birch, ironwood and red maple within select area boundary.

Clear Cut with reserves Area

Cut all merchantable aspen, white birch, red maple and ironwood within the clear cut area. Cut orange marked oak and pine. Do not cut spruce or balsam fir. Sever all non merchantable mixed hardwood and ironwood stems 1 inch and larger.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.

SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H03-11
 Section, SENE, NESE, sec. 22 T38N, R9W

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|----------------|------------------|--------------|------------------|----------|
| MIXED HARDWOOD | 85 cords | \$20.00/cd | | |
| RED OAK | 85 cords | \$12.00/cd | | |
| RED OAK | 3MBF | \$200.00/MBF | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions:

Select Cut Area

Cut all orange marked oak and mixed hardwood. Utilize all pulpwood down to a 4 inch D.I.B. Utilize saw timber to a 10 inch D.I.B. All products sold as saw timber will be scaled on the landing. Care should be taken to not damage residual standing timber.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.


SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

Sawyer County State Lands Timber Sale
Benson Creek Fisheries Area
SENE, NESE, SEC. 22 T38N R9W
TRACT H0311 _____ 17 ACRES



Legend

- Property_Boundary
-  SALE AREA

1 inch = 0.25 miles

SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H04-11
 T38N R7W Secs, 6,7
 T39N R7W Sec 19

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|-----------------|------------------|-------------|---|----------|
| Aspen | 895 cds | \$20.00/cd | | |
| Mixed hardwoods | 545 cds | \$20.00/cd | This volume contains approx. 6 cds of basswood | |
| Fir/Spruce | 20 cds | \$20.00/cd | | |
| Red Pine | 60 cds | \$30.00/cd | This volume contains approx. 2 cds of White Pine and 8 cds of jack pine | |
| | | | | |
| | | | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions:

Clear Cut Area

Cut all merchantable aspen, mixed hardwoods, jack pine and ironwood within the clear cut area. Cut all spruce and balsam fir with 3 or more 100 inch sticks. Do not cut any white pine or Red pine unless marked with orange paint. Sever all non merchantable mixed hardwood, aspen and ironwood stems 2 inches and larger. Utilize all pulpwood to a 4 inch D.I.B. Utilize all saw timber to a 10 inch D.I.B. All products sold as saw timber will be scaled on the landing and converted to cords equivalent. Do not cut Oak. Do not cut any trees in the areas marked with a green paint line.

Select Cut Area

Cut all orange marked red pine and white pine in the select marked area. Utilize all pulpwood down to a 4 inch D.I.B. Utilize all saw timber to a 10 inch D.I.B. Discriminate against ironwood when ever possible by cutting or running over. Do not cut Oak. All products sold as saw timber will be scaled on the landing and converted to cords equivalent.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.

SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS


As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

Tract H 04-11

Sawyer County State Lands Timber Sale
Eddy Creek Fisheries Area
E1/2 SW 1/4 Sec. 6; NENW Sec. 7; T38N R 7W
E1/2 SW1/4 Sec. 19 T39N R 7W



Ashegon Fire




*SALE AREA
NORTH PORTION

24 19
25 30

MAP 1

*SALE AREA
SOUTH PORTION



01 06
12 07
State Highway 70

Red Line

06 05
07 08

Legend

- Green Tree Retention Area
- Clearcut Area with Reserves
- Drainage
- Select Cut Area

1 inch = 0.25 miles

MAP 2

SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H05-11
 Section, 16 T38N, R7W

| |
|---|
| For questions on this sale, please contact: Randy Sobraliski at the Hayward office. 715-634-9658 ext.3510 |
|---|

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|----------------|------------------|-------------|---|----------|
| ASPEN | 55 cords | \$20.00/cd | | |
| MIXED HARDWOOD | 25 cords | \$20.00/cd | | |
| BASSWOOD | 20 cords | \$5.00/cd | Volume contains approx. 2 MBF of saw logs | |
| OAK | 30 cords | \$12.00/cd | Volume contains approx. 2 MBF of saw logs | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions:

Select Cut Area

Cut all orange marked oak and mixed hardwood. Also cut all merchantable aspen and ironwood within the select area boundary. Utilize all pulp wood down to a 4 inch D.I.B. Utilize saw timber down to a 10 inch D.I.B. All products sold as saw timber will be scaled on the landing and converted to cords equivalent.

Clear Cut with reserves Area

Cut all merchantable aspen and mixed hardwood. Do not cut spruce, balsam fir or oak. Sever all non merchantable mixed hardwood and ironwood stems 2 inches and larger. Utilize all pulp wood down to a 4 inch D.I.B. Utilize saw timber down to a 10 inch D.I.B. All products sold as saw timber will be scaled on the landing and converted to cords equivalent.

Aesthetic Zone All tops and slash shall be removed with-in 50 feet of Ortwig Ln. and lopped to with-in 18 inches of the ground with-in 100 feet of town road. Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.


SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

State Lands Timber Sale
 Beverly Lake Fisheries Area
 SWSW, SEC. 16 T38 R7W
 Tract H0511 Sale# _____ 13 Acres



SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H02-12
 N1/2SW1/4, S1/2 NW1/4, SESW Sec,6 T37N R7W

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|----------------|------------------|-------------|--|----------|
| ASPEN | 375 | \$20.00/cd | | |
| MIXED HARDWOOD | 110 | \$20.00/cd | This volume contains approx. 7 cords of Basswood | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions: **Frozen Ground only**

Clear Cut with reserves Area

Cut all merchantable aspen, mixed hardwood and ironwood within the clear cut area. Utilize all pulpwood to a 4 inch top diameter. Sever all non merchantable aspen, mixed hardwood and ironwood stems 2 inches and larger. Do not cut any oak or white pine.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's Chapter 30 permit may be required for this sale.

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.


SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

Sawyer County State Lands Timber Sale
 Weirgor Wildlife Area
 S1/2 NW1/4, N1/2 SW 1/4, SESW, SEC. 6 T37N R7W
 TRACT H0212 _____ 41 ACRES



Legend

-  Green Tree Retention Area
-  SALE AREA
-  Drainage

SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H01-13
 W1/2NE1/4, N1/2SW1/4, W1/2SE1/4 SECTION 18.T41N R9W

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|----------------|------------------|--------------|------------------|----------|
| ASPEN | 400 cds | \$20.00/cd | | |
| Mixed hardwood | 160 cds | \$20.00/cd | | |
| Basswood | 50 cds | \$5.00/cd | | |
| Balsam fir | 35 cds | \$20.00/cd | | |
| | | | | |
| Mixed Hardwood | 8 MBF | \$96.00/MBF | | |
| Basswood | 4 MBF | \$100.00/MBF | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions:

All logs will be scaled on the landing, piled small end out, prior to shipping.
 Any slash within 50 ft. of town roads to be lopped and scattered within 18 inches of the ground.

Select Cut Area

Cut all orange marked trees, cut all ironwood and merchantable aspen within select area boundary. Utilize all pulpwood to a 4 inch top and saw logs to 10 inch D.I.B.

Clear Cut with reserves Area

Cut all aspen, mixed hardwood, ironwood and balsam fir within the clear cut area. Do not cut spruce. Sever all non-merchantable hardwood and ironwood stems 2 inches and larger. Utilize all pulpwood to a 4 inch top and saw logs to 10 inch D.I.B.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ are prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.

SURVEY CORNERS

Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

Sawyer County State Lands Timber Sale
Kissick Wildlife Area
W1/2 NE, N1/2 SW, W1/2SE, Sec. 18 T41N R9W

TRACT H0113 _____ 57 ACRES



Gate

12-7
13-18

26-17
18-17

BLUE LINE

RED

BLUE

BLUE LINE

RED

Text

13-18
24-19

18-17
19-20

Legend



Select Cut Area



Clearcut Area with Reserves

1 inch = 0.25 miles

SAWYER COUNTY STATE LANDS
 TIMBER SALE PROSPECTUS
 TRACT # H03-13
 SW1/4 NW1/4, NW1/4 SW1/4 SECTION 8 T40N R6W
 NE1/4 SE1/4, SW1/4 SE1/4 SECTION 7 T40N R6W

For questions on this sale, please contact:
 Randy Sobraliski at the Hayward office.
 715-634-9658 ext.3510

| Species | Estimated Volume | Minimum Bid | Cruiser Comments | Bid/Unit |
|----------------|------------------|--------------|------------------|----------|
| ASPEN | 220 cds | \$20.00/cd | | |
| MIXED HARDWOOD | 240 cds | \$20.00/cd | | |
| RED OAK | 130 cds | \$20.00/cd | | |
| | | | | |
| RED OAK | 12 MBF | \$200.00/MBF | | |
| MIXED HARDWOOD | 2 MBF | \$96.00/MBF | | |
| | | | | |

Total Bid _____

Harvesting Prescriptions: Frozen Ground logging only
 All logs will be scaled on the landing, piled small end out, prior to shipping.

Select Cut Area

Cut all orange marked trees, also cut all merchantable aspen and ironwood within the select area boundary. Utilize all pulpwood to a 4 inch top and saw logs to 10 inch D.I.B.

Clear Cut with reserves Area

Cut all aspen, white birch, red maple and ironwood within the clear cut area. Do not cut oak. Sever all non-merchantable mixed hardwood and ironwood stems 2 inches and larger. Utilize all pulpwood to a 4 inch top and saw logs to 10 inch D.I.B.

Aesthetic Zone Care should be taken during the harvesting operation to minimize any detrimental effects to the soils. Before the timber sale is closed, all forest skid trails and logging roads used in the harvesting operation must be leveled to presale conditions or better.

Integrated Resource Considerations -

All existing and future logging roads must be kept free of slash and logging debris. Any new forest road location or construction is subject to review and approval by the D.N.R. Forester. All slash must be removed from adjacent private land ownership, and any slash or logging debris accumulated on the landings must be lopped and scattered. Depositing slash and/or logging debris in any wetland or RMZ is prohibited. Decking of cut forest products will not be permitted on any town road right-of-way, unless prior approval is granted by the Town Chairman.

BMP's

Wisconsin's Best Management Practices (BMP's) for Water Quality are required on all State timber sales. BMP manuals are available from your DNR office. When constructing roads, cutting timber, or skidding timber near or across wetlands, lakes, streams, or intermittent drainages know your BMP's and follow them.

LITTERING

Sale area shall be kept free of litter at all times. Enforcement action will be taken for noncompliance.

SURVEY CORNERS


Do not disturb survey corners, monuments, or surrounding witness trees.

ROADS

As per State Statute 86.02 contractor is liable for damages made to town, county, or state highway. As per SS. 86.04, timber or other objects cannot be placed on any highway right-of-way. It is recommended that landings be constructed no closer than 100' town, county, or state highways.

Sawyer County State Lands Timber Sale
Chippewa Flowage Properties
SWNW, NWSW Sec 8; NESE, SWSE, NWSE, Sec. 7 T40N
R6W

H03-13



Legend

-  Clearcut Area with Reserves
-  Select Cut Area

1 inch = 0.25 miles

